



	Bunker		<u>ter Manageme</u>	ent			
		Maximum Measured Flows	Maximum Measured Flows	Measured Flow	Maximum Measured Flows	Proposed Design	
Location	Rationale	(Erikson, cfs) ¹	(Erikson, gpm) ¹	Dates (Erikson)	(Riley, gpm) ²	Flows (gpm) ³	Design Remarks ⁴
		Phase I Loca	ations				* * * * * * * * * * * * * * * * * * *
Level	This was a second of the secon	,		· · · · · · · · · · · · · · · · · · ·	,		,
Itz Drift	Assess effectiveness of Milo Creek diversions						
lomestake Drift Level	Assess effectiveness of Milo Creek diversions			L	L		l
Becker	Measure tributary flows from ore chutes. Discharges to the Loadout			· · · · · · · · · · · · · · · · · · ·	ı		T
	Area @ 9 Level.	0.29	130	2/83 to 9/84	113	228	4 x 36 cutthroat
Villiams	Russell Tunnel, and various ore chutes and raises downstream from the New East Reed Flume. Discharge is tributary to the Loadout Area @ 9 Level.	0.42	188	2/83 to 9/84	192	336	4x36 cutthroat, cleaned cland operating
West Reed	Flow originates from ore chutes, caved and flooded drifts west to the	0.72	100	200 10 0/04	102		and operating
	Cherry Raise area. Flow is normally tributary to the Becker Weir, occasionally tributary to the Reed Tunnel due to build-up downstream						trapezoidal flume was us
	of the West Reed Flume.	0.046	21	2/84 to 9/84	29	51	2x18 proposed
3 Level							
Loadout Area @ 9 Level							12" trapezoidal weir used previously, 4x36 cutthro
	Tributary to Kellogg Tunnel flume.	1.2	539	2/83 to 9/84	620	1085	proposed
stanley Ore Chute	Drains a portion of the Guy Caving operation. Flow is tributary to the	0.005		0/00 +- 0/04		00	bucket & stopwatch, has lot of debris and floods u driftwalls
/an Raise or Cherry Raise	Loadout Area @ 9 Level.	0.025	11	2/83 to 9/84	11	20	30 degree v-notch weir
an haise or Cherry haise	Measures flow coming down the Cherry Raise from below the 5 Level. Tributary to the Loadout Area @ 9 Level.	0.067	30	12/83 to 9/84	33	58	used previously, 2x18 cutthroat proposed
lo. 2 (White) Raise Pumps		NA NA	NA NA	NA	Approx. 550	NA NA	NA NA
Cellogg Tunnel	Measures all discharge from the Bunker Hill Mine.	5.4	2424	1/83 to 8/84	2428	4249	existing 12° parshall flum
Barney Switch	Measures drainage from the west end of the mine including areas around the No. 3, Orr, and Skookum Shafts. Tributary to Kellogg						
TO SET COMPT COMPT OF THE COMPT AND THE	Tunnel Flume	0.85 Phase II Loc	381	12/83 to 9/84	253	668	4x36 cutthroat flume
Level		Phase II Loc	ations			er, in the care blesses are	1. 20 5 5 500, 250, 250 50 50 50 50 50 50 50 50 50 50 50 50 5
lew East Reed Flume	Measure discharge from exploration drill holes, rock bolt holes, and		i	1	i -		1
Con Last 11000 1 Idillo	fractures in the New East Reed Drift. The drainage area is isolated from overlying and underlying mine development. Flow is tibutary to Williams Weir. The need for this flume will be based on comparison of historic and current flows at Williams Weir.	0.11	49	1/84 to 9/84	69	121	4x18 cutthroat flume
Russel Dam Weir	Flow to this weir is controlled by low dam blocking the Old East Reed Drift. Discharge originates from drill holes and fractures in the Old	0.11	73	1704 10 3/04	35	121	
	East Reed Drift and from an ore chute in the Governor Cross-cut. Flow is tributary to the Williams Weir. The need for this flume will be based on comparison of historic and current flows at Williams Weir.	0.12	54	12/83 to 9/84	53	94	30 degree v-notch weir used previously, 2x18 cutthroat proposed
0 Level		·					
eadwood Side, or Jersey	The need for this flume will be based on concentration and flow data obtained from No. 2 pump. Approximately 20 - 30 gpm coming from 10 level.						

Based on the higher of Riley or Erikson maximum flows times 1.75 factor of safety.
 Flumes that required installation are in bold.

Flow vs. Head for 4x36 and 8x36 Cutthroat Flumes



Flow vs. Head for 1x18, 2x18, and 4x18 Cutthroat Flumes






Figure Al. Head-discharge relationships for various flumes and weirs.